

ROOF FRAMING PLAN

1:100



SIDE WALL ELEVATION - GRID A (GRID B SIMILAR, BR2 x 4 PER WALL)

1:150



TYPICAL PORTAL FRAME - GRIDS 2 TO 4

1:150

END WALL ELEVATION - GRID 1

1:150



END WALL ELEVATION - GRID 5

1:150

MEMBER SCHEDULE

MARK	SECTION	DESCRIPTION
C1	250UB31.4	Portal column, grids A & B
R1	250UB25.7	Portal rafter, eave to ridge
EC1	150x150x5.0 SHS	End wall column, grids 1 & 5
DH1	100PFC	Roller door head, grid 1
PJ1	89x89x3.5 SHS	Personnel door jamb, grid 5
PH1	89x89x3.5 SHS	Personnel door head, grid 5
P1	Z20019	Roof purlin, 6 rows each side
EP1	C20019	Eave purlin, simple span
G1	Z15015	Side wall girt, 3 rows each wall
G2	C15015	End wall girt, between columns
BR1	M16 ROD	Roof cross bracing, end bays
BR2	M20 ROD	Side wall cross bracing, end bays
S1	89x89x3.5 SHS	Ridge strut, braced bays
FB1	50x50x5 EA	Rafter fly brace

GENERAL NOTES

1. Steel grade 300PLUS U.N.O., hollow sections C450L0.
2. Roof pitch 5 deg, eave height 4500 above FFL.
3. Purlins Z20019 lapped 15% of span at frames.
4. Rod bracing with turnbuckles, end bays.
5. Fictitious project - for demonstration only.

PROJECT	**RURAL MACHINERY SHED 24 x 12 m**
	SAMPLE - FICTITIOUS PROJECT
SHEET	FRAMING PLAN, SECTION AND ELEVATIONS
PREPARED	SERGEI GRISHUTOV - QUANTITY SURVEYOR
SCALE	AS SHOWN @ A3
DATE	NOV 2026

NOT FOR CONSTRUCTION

REV A

S1